

SYVERSON

TILE & STONE

HOMEOWNER EXPECTATIONS GUIDE TO NEW STONE COUNTERTOPS

We have prepared this important information for your benefit and reference. It is intended to guide you through the process and set the right expectations to ensure your satisfaction.

PRODUCT INFORMATION

Quartz and Granite products have remarkable beauty and natural characteristics that make them very hard and durable, they come in a huge array of colors and patterns, and they are easy to maintain, for which they have become the favorite choice for countertops. Slabs may vary in gauging, coloration, shading, markings, and textures. All of these characteristics add to the uniqueness of the stone. Syverson Tile & Stone will not guarantee that all pieces will be consistently uniform. Granite, quartz, and other stones may have fissures that have been filled with an epoxy resin at the quarry or at the fabrication shop. Potential manufacturing, installation problems or material availability may occur. Weak spots and fissures in granite may be more noticeable if they separate. Additional cracks may appear after installation, particularly if settling in the home that causes movement or stress on the countertop occurs. Lighting and installation planes will affect the appearance of the countertop surface.

Granite and Natural Stone

Granite is a natural stone that contains natural characteristics throughout the slab, such as

- Color, pattern, and particulate variation within the same slab.
- Fissures or tiny hairline crevices which may look like cracks.
- Pits or air gaps created during rock formation.
- Inclusions or cluster of mineral deposits of any color during rock formation.
- Water lines.
- Blemishes and dull spots.

These are not flaws or defects and will not impair the function and durability of the material. The overall appearance of the slab is polished and mirror like, but your countertop will surely

contain some. The extreme hardness, which approaches that of diamonds, makes granite uncommonly durable and extremely appealing for use every day in the home. The sample used to make your color selection is only a representation of the tone and pattern but, because each slab is different, variation in color and pattern should be expected in the slabs used to produce your countertops. It is recommended to take the time to physically view the color and characteristics of the stone that will be transformed into your countertop.

Unsealed, granite can absorb stains such as oil, which can cause dark spots or discolorations. As a standard, we will apply a sealer that will protect your countertop for up to 1 year, then it is up to you to re-seal every 6 to 12 months.

Quartz

Quartz surfacing is composed of natural materials, 90-93% of which are the finest quartz and granite aggregates. This natural stone product has taken the best of what nature has to offer in terms of the durability and the beauty of stone. Through extensive engineering, a manufacturing process was developed utilizing intense heat and pressure to increase the color consistency, stain resistance, and overall strength of this natural stone product. Being that quartz is non-porous; it will not require the use of sealants and it withstands normal wear and tear beautifully. Professionally developed colors are computer-calibrated to maintain consistency allowing designers and customers to make a close selection from samples, although it is still intended only as a representation of the color. The slab used for your countertop will not be identical to the sample used to make your selection, as there may be some variation in particulate, color, and shading, especially in the designs that look like granite or marble. You may also find concentration of crystal, spot, pooling, small pits or veining not present in the sample. These are not considered defects or flaws and will not interfere with the performance of the product.

Material Viewing, Approval and Layout

Syverson Tile & Stone offers our customers with the option to approve the slab that will be used for the installation. We understand that natural stone can vary in color from the sample that you saw in the showroom, or at the supplier's location. After completion of the template, Syverson Tile & Stone will provide an actual photo of your slab on our PathFinder program. The intent of the software is to demonstrate the grain flow and color variation throughout the countertop with the specific slab you picked out. During the cutting process, Syverson Tile & Stone will consider the vein direction and will attempt to produce the finished product with vein patterns running in one direction, when possible.

Availability

We will notify you as soon as possible if your project is going to be affected by material availability. Syverson Tile & Stone will not provide compensation to you for any delays due to this situation.

PREPARATION AND WHAT TO EXPECT

Adequate Support

At least **70%** of the total countertop must be supported by cabinets, an island, knee wall, etc. The type of surface dictates the amount of overhang permitted on a countertop.

The countertop can support the following overhang over a 24" deep base cabinet without additional brackets or corbels:

- 10" Granite or other natural stone countertop
- 15" Quartz countertop

Brackets, corbels, and sometimes legs should provide adequate structural support for overhangs, in excess of the above guideline. Supports are usually installed by your carpenter and need to be installed prior to installation of the new countertops.

New or existing cabinets must be structurally sound to withstand the weight of the countertop. Lazy Susan, corners and other spaces should have added wall cleats for support.

If you have any questions or concerns about supporting your countertop, it would be best to address the issue at the time of the design, but the final verification will be done by our Measure Tech at the time of measure. He will recommend the kind of support needed and verify that your cabinets are structurally strong.

Cabinets

Cabinets must be plumb, level and permanently secured to the wall or floor.

Cabinets should be as level as possible because the countertop must lie flat within 1/8" to eliminate stress on the corners, cut-outs, and seams. Consider the help of a professional woodworker to ensure that your cabinets are plumb, level and square. Keep in mind that your countertops will be as level as your cabinetry is. It is recommended that you do this before the measure. If your cabinets are slightly out of level, we may require placing shims between the cabinet and the countertop to bring up to level, however, in other instances, we may have to install the countertop flat according to the trajectory of your home and tile. We will not be able to install on excessively unlevelled cabinetry. Gaps and shims may be visible, so you may want to consider having them covered with decorative trim by your carpenter or contractor.

New upper cabinets that will rest on top of the countertop must be installed after the installation of the countertops. If you have existing upper cabinets, you may need to have your carpenter lift them to allow for countertop install. Cabinets on both sides of the stove must be installed so that they are on the same 'plane' – front and back; front-top and bottom, especially if there will be a slide-in stove. Cabinet refacing needs to be done *before* the countertops are measured. New flooring should be done *before* the countertops measure if the cabinets will be moved and reset in place. New flooring installed without disturbing existing cabinets is ok, but keep in mind about dishwasher and stove height that have remain below countertop level.

The Golden Rule

All cabinetry, including panels, doors, and end panels must be completely and *permanently* installed prior to the date that is scheduled to be field measured.

Never move, add, or adjust the cabinets after our Measure Tech has done the measure.

The new countertops will not fit and can result in delays and costly remakes for you.

If the cabinets are incomplete or not ready at the time of measure, we will not be able to complete it, we will need to return to re-measure and a trip charge will apply.

Sinks

Size (and shape) matters! Some sinks may be too big for your cabinet, so consider the cabinet *clearance* when selecting a new sink, especially for undermount installation.

Get the sink specs provided by the manufacturer prior to purchasing to verify if it works for you.

Check that the cabinet is at least 3" wider than the *overall* sink dimensions (including the rim) and that the depth of the sink does not interfere with the plumbing pipes.

Some sinks like banjo style or 'D' shape may not fit and will not allow for multiple faucet holes.

Tip out trays and recessed door cabinets may also interfere with the size and shape of the sink.

The Golden Rule

All sinks **must** be on the job site prior to the date of field measure, unpacked and inspected, except for sinks provided by Syverson Tile & Stone.

Farm and apron sink should be dry fit **prior to field measure** into correct position, plumb and level with the sink cabinet, but not yet siliconed or glued to the cabinet below.

All cut out information, digital and paper templates must be available at the time of field measure. Our Measure Tech will be unable to finalize the measure if sinks and templates are not on site and a return trip may be required resulting in additional trip charges and delayed installation.

Sink Cut Outs and Reveals

Some sinks offer multiple cut out template options, like *Reveal*, *Negative Reveal* or *Flush*, while other sinks offer only one option. A *reveal* cut out will be slightly wider than the sink opening, 'revealing' the rounded rim of the sink. A *negative reveal* cut out will be slightly smaller than the sink opening, and it will have a slight overhang. A *flush* cut out is the same size of the sink opening. However, we have found that what *flush* means for one supplier, it may mean differently to another, and some *flush* cut outs still show a little bit of the rim. If you are very specific about the type of reveal you want, look for sinks that provide a manufacturer template with that type of cut out. Check with the supplier or directly with the manufacturer prior to purchasing and look for photos of an installed sink. It is also very important that you are present at the measure and that your sink, with paper and digital template, is available at that time, so our Measure Tech reviews the options with you. **Syverson Tile & Stone will not alter any template** recommended by the manufacturer, and we will not be responsible for the way the cut-out fits when opened according to the template provided. Cheap sinks will usually bring problems with cut out templates and uneven rims, so we recommend you purchase from a known manufacturer.

The cut out for sinks and cooktops opened at the fabrication shop is part of the production process and results in waste that is thrown away 100% of the time immediately after the cutout is made. The waste is usually irregular in shape, unfinished and sharp. **Please note that cut outs for sinks and cooktops that are done in the shop cannot be provided.** Cut outs opened on site will be left at the request of the customer. The pieces are rough-cut, unfinished, and not square. The installers will not polish or finish the edges on site, as an additional labor cost for this service applies.

Faucets

As with sinks, not all faucets may work with your countertop design. Some faucets may be too tall when there is a snack bar or ledge behind, they may have a lever too angled, or have a handle that will not turn properly all the way back because it hits the backsplash. Some faucets may have multiple holes that will not work with your sink, so please check if the faucet will work with your sink prior to purchasing.

The Golden Rule All items to be mounted in the countertops **must** be on the job site prior to the date of field template, so our Measure Tech is able to check and verify that they work and fit in your countertop: faucets, soap dispensers, air gap, water dispensers, etc. (except for items provided by Syverson Tile & Stone). All cut out information, templates and specifications must be at the job site prior to field measure as well. Changes in specifications after field template will result in additional trip charges and delayed installation.

Appliances

Cooktop, slide in stove and vents that go on the countertop need to be on site at the time of measure and specs sheet available. All appliances including dishwashers, stoves, and refrigerators must be in place at the time of the field measure. Our Measure Tech will let you know if you need to remove any appliance for the countertop installation.

Backsplashes

To ensure proper fit, some backsplashes may have to be measured after the countertop is installed. If the job includes full height splash, upper cabinets, hoods, and range microwaves must be installed at the time of measure of the full height backsplash.

If the walls are bowed or uneven, there will be gaps behind the backsplash because the stone will not bend. Sometimes our crew will be able to caulk between the top of the splash and the wall, but there are occasions that this will need to be done by whoever is finishing or painting the wall surface. If there is existing wall tile, it may not be possible to follow the exact line of the tile when installing a new backsplash under the tile. Our installers will not grout the gap between the tile and backsplash. This is to be completed by a tile installer or the customer. Sometimes, the splash may need to be installed slightly over the tile. Our installers will not remove tile to install the backsplash. Electrical outlets must be prepped and ready for

countertop measure and should not be moved. Our installation crew will not place the boxes and wiring in the outlets, nor will the plates be installed.

Seams

Most stone countertops will have seams and they should be seen as integral part of your project. Our installers will attempt to make the seam as tight as possible, but all **seams are visible to the naked eye and can be felt**. Seam width will vary from stone to stone. The acceptable industry standard for seams is up to 1/8" wide and 1/32" rise for every 12" of seam. The Measure Tech will recommend seam location and will review with you at measure, but we reserve the right to change placement at fabrication, if necessary. During fabrication, great care is taken to lay out the slab to minimize waste, blend the color and pattern, and place the seams in the best location for structural integrity and visual aesthetics. The natural variations of granite make it impossible to guarantee a match or blend in pattern or color from one piece of counter to the next. Seam location factors include job layout, slab size, crew safety, and jobsite accessibility. Stone with a defined veining direction may require additional seams to ensure vein direction for all pieces is consistent. Our goal is to please you and fulfill your specific requests at the best of our abilities with the limitations at hand.

Plumbing, Electrical and Woodworking

Other professionals may be considered for your remodeling project: a plumber to install shutoffs and to reconnect your sink and dishwasher, add plumbing pipes, etc.; an electrician to connect vents, outlets, stoves; a carpenter to lift or remove upper and appliance garage cabinets, to level cabinets, to install supports and brackets, to add a trim, etc.

Our crews are certified stone installers, but they are not certified in other trades and may not even have the right tools needed to do quality work. Syverson Tile & Stone is not responsible and cannot be held liable for the functionality of existing plumbing lines, fixtures, or equipment. Also, it is important to know that if the plumbing reconnect is done too early and it results in a dropped sink, this would cause a void in the installation warranty.

Tear Out

If you are doing the tear out yourself, make sure to remove your existing countertops, sinks, faucets and appliances completely prior to the arrival of our crew. The cabinets must be flat, plumb and free of nails and debris. If Syverson Tile & Stone is doing the removal of your existing countertops, the water shut-off valves must be shut off prior to our arrival. Please be aware that, even the most experienced Measure Tech or installer, is not able to guess what's underneath and behind existing countertops, so there is a slim chance that the cabinets are so out of level after removal that we will not be able to install your countertops until they are fixed. Another thing to consider is that the cabinets may not be as level as desired, so gaps after installation may be expected. Sometimes, a trim done by your carpenter may be an option.

Existing tile often comes dislodged when removing the existing top. The installer is not responsible for replacing dislodged or broken tile. Mirrors in bathrooms that are affixed to the wall and resting on or 1" above the top of the existing backsplash or countertop must be

removed before tear out. Any damage to mirrors not removed is responsibility of the homeowner. Our installers will not remove mirrors. If our installers are doing the tear out, they will haul away the old countertops. Indicate the installers if you wish to keep the old top *prior* to removal. In some instances, it will not be possible to remove them whole and the installers will have to cut them in pieces.

Incidental Damage

Final wall painting or other preparation should not be completed prior to installation, if at all possible. Care will be exercised during the countertop installation, however, scrapes, punctures, or digs to wall surfaces or cabinetry are possible and sometimes unavoidable in the work area and occur from time to time. These items are considered incidental damage and are the customer's responsibility to repair. Be assured, our installers will always exercise considerable effort to prevent incidental and minimize incidental damage at all times.

Cancellation and Returns

Your countertops are custom made and are not returnable and the purchase price cannot be refunded. Cancellations are not accepted after your approval has been received after measure.

Customer Present at Measure

The customer (or designated decision-maker, like designer or contractor) must be present at the time of field measure, and is responsible for reviewing and approving all the details of the countertop with the Measure Tech. Without the customer or decision-maker approval present, Syverson Tile & Stone will not be able to proceed and there may be delays in installation scheduling. All decisions regarding countertop design, edge selection or any other design-related items must be made prior to the date of measure with your designer or contractor.

The field measure and final drawing overrides all previous drawings.

Final Pricing

Your initial purchase order is an estimate of the projected price of your countertop project. The final price will be determined after the field template has been completed and we have final dimensions, square footage and confirmation of selections and services.

The final quote price overrides all previous estimates and quotes.

Customer Approval

After the field measure, our Syverson Tile & Stone customer service representative will send the final quote and drawings to you or your designer for you to review, approve and sign. Our green light to proceed with production and installation schedule is when we receive the signed final quote and final drawing.

THE INSTALLATION PROCESS

Preparing for the Measure

The field measure is the KEY step for best results, and we need you to be part of it. Your new countertops will be fabricated and installed to fit correctly according to the field measure specs, details, and your approval.

Quick Checklist

- Customer must be on site for decisions and approval.
- Color, edge, and design must be finalized prior to measure.
- Cabinets must be completely installed and secured permanently.
- Sinks and templates on site and unpacked.
- Faucets, soap dispenser, filter, air gap must be on site and with specs.
- Cooktop, slide in stove, countertop vents must be on site and with specs.
- Farm or Apron sinks must be installed.
- Remove all items from the countertops prior to the measure.

Cabinets

Prior to field measure, all cabinetry, including end panels, doors, and walls must be completely installed plumb, level and square and permanently secured to walls and floor. Cabinets that will rest on top of the countertop (like appliance garage), must be removed, and installed *after* the installation of the countertop. Cabinets **must never be moved or lifted after a measure** is completed as countertops will not fit any longer.

Sinks, faucets, and appliances

Sinks, faucets, soap dispensers, filters, air gaps, cooktops, vents, slide in stoves and all items to be mounted in the countertops must be on the job site prior to the date of field measure.

Customer is responsible for unpacking and checking for damage, prior to our arrival.

All cut out information and specs and sink templates must be on site at measure. The exception applies when Syverson Tile & Stone provides the sink and/or faucet.

Apron and farm sinks must be installed prior to field measure.

Removal of existing countertops

Most of the time, Syverson Tile & Stone will use digital templating system, so countertops can be measured without removing existing tops. However, when measuring with tops on, not all imperfections can be found, like inadequate support or cabinets not level; neither can our measure crew guess what is behind and under existing tops. Customer should expect wall gaps, gaps between cabinet, and countertop shimming at installation. Splashes that may not be high enough to cover old splashes line marks or butt tightly against wall tile. The above applies whether Syverson Tile & Stone or the customer remove the existing countertops.

Final Selections

All decisions regarding edge profile, thickness, color, and countertop design must be made prior to the date of measure. The Syverson Tile & Stone measuring team cannot make design decisions. It is suggested to have a mock-up on site of unique island layouts to facilitate the measuring process. Cardboard or plywood is suggested.

Customer Confirmation and Approval

The customer or designated decision maker over the age of 18 **must be present** at all times during field measure, and will be responsible for approving all the details of the countertop and confirming all selections. The field template supersedes all previous drawings and dimensions.

Preparing for the Installation

The homeowner or designated decision-maker (over the age of 18) should be available during the entire duration of the installation and must be present at the end of the installation to inspect the countertop.

Quick Checklist

- Plumbing and electrical disconnected prior to install and reconnected at least 12 hours after installation.
- Sinks, faucets, air gaps, fixtures and appliances that go on the countertop, unpacked and ready in area.
- Countertops removed, free of nails, flat and plumb (if you will tear out).
- All items on countertops removed (if Syverson Tile & Stone will tear out).
- Drawers and all items in sink cabinet removed.
- Children and pets away from the area at all times.

Other Important steps

- Remove all items under the kitchen sink and any breakables from other base cabinets. We suggest you cover with cloths the rest of the items to minimize cleaning afterwards.
- Please keep pets and children completely away from the work area due to risk of injury, noise, dust, odors.
- Designate a path and doorway for installers to come and go with the heavy materials.
- Show the installers a designated work area for cutting and adjusting, if necessary. We suggest a garage or a similar area.
- Driveway should be clear, free of snow, ice, and mud.
- Take a break from cooking. While your kitchen is out of service, order take-out or set up a temporary food prep area in another room.

Cutting and Adjusting of the Countertops

The installation of stone countertops and splashes will require that the installer trim the countertops and splash at the installation site to ensure the best possible fit. This procedure is usually performed on the driveway or garage, depending on weather conditions. If it is raining, a covered place for the installer to work must be available or the installer might have to reschedule the installation.

Sinks, Faucets and Appliances

Our crew will install the undermount sink using the most appropriate method that works for your project. They will also install a dishwasher bar or other method according to what works for your project. Our installers will not install drop-in sinks, cooktops, faucets, vents or any other fixture, but will need to test fit every item that goes on the countertop, including the plumbing for a vessel sink. You need to have all of the sinks, faucets, and appliances that go on the countertop and the plumbing pipes for vessels sinks on site and available at the time of installation. If we need to return to adjust any cut out for items not available at time of install, we will open a service call request and fees will incur.

Installation Sign-off

We recommend the customer to be present to inspect the countertop after installation. If you are not completely satisfied with the installation of your countertop, please contact Syverson Tile & Stone immediately, preferably before the installer leaves the location.

Clean Up

Installation of a countertop is a construction process and residual dust should be expected. The customer may want to drape or cover areas to help contain the dust to the construction area. The job site will be left in broom-clean condition.

Safety

For safety reasons, children and pets must be kept out of work area, or leave the residence for the duration of the install. Heavy items, odors, dust, and fumes are part of the installation. For safety reasons, our installers cannot remove their steel-toed shoes or wear fabric booties. They will cover the area to protect the floor.

Delays

During transportation, a top can break sometimes. If this were to occur, Syverson Tile & Stone will repair or remake the top and prioritize the installation of the new top within a few days. Delays may occur in order to have additional stone supplied to remake the pieces. Customers planning parties or events in their home should be cautioned to provide several weeks of cushion before hosting an event in their home as delays on major construction projects are common and occur for unforeseen reasons. No compensation or reimbursement will be provided for delays occurring due to a broken top or splash.

Weather Conditions

We appreciate your understanding if we need to cancel your installation due to weather conditions that put in risk the safety of our installers on the road or when carrying the heavy stones. Extreme weather, fog, snowstorms, and blizzards and freezing temperatures are sometimes factors that determine a ‘Snow Day’. We will advise you with as much anticipation as possible, but sometimes we cancel at the last minute, hoping that we do not have to reschedule your project. We will not provide any compensation for cancellation due to weather.

After Installation of your Countertops

What to do (and not to do) after installation

- Connect your sink and garbage disposal **at least 12 hours** after installation.
- Do not clean, touch, or use water on any newly silicone or caulked areas for at least 12 hours (or they will remain white and not turn clear).
- Do not move or bump against any newly installed tops for at least 24 hours.
- Wait 24-48 hours to install tile splash.

General Precautions

- Avoid standing on the countertops.
- Do not move heavy items across the tops.
- Treat your countertops with care. Impact can produce chips or dents.
- Use a trivet or pad to protect from heat damage and thermal shock for hot pots and pans, fryers, crockpots, and such appliances.
- Sudden changes of temperature and cold drafts in a warm area may cause thermal shock crack.

Manufacturer Warranty

Your countertops are covered against manufacturing defects according to each specific brand. Any work required under the terms of the product warranty, will be performed by us in accordance with the manufacturer procedure. We will also administrate any necessary claim on your behalf. Some manufacturers provide replacement of material only in which case, Syverson Tile & Stone will charge for fabrication, installation and any other labor required. Please refer to the specific warranty for exact coverage and exclusions. Chips, fissures, crevices and cracks are not defects, but natural characteristics of the stones. Sometimes we fill them in the shop, depending on the size. If caused at transportation and handling, they will be repaired at installation.

Installation Warranty

Your installation is guaranteed for one year from the date it is completed for the components of the job, which includes initial fit and hard seams.

Our installation warranty **does not** include:

- Chips, dents, damage by impact.
- Separation of seams or damage caused by house or cabinet settlement or movement, lack of adequate support or uneven cabinets or flooring.
- Cracks.
- Normal Wear and Tear.
- Heat Damage.
- Regular maintenance such as cleaning.
- Renewal of caulk, silicones and resins.
- Physical damage or abuse.
- Fallen or shifted sinks by hooking plumbing too soon after installation.
- Replacement of caulk and silicones smeared or not turning clear due to cleaning too soon after installation.

Care and Maintenance

Quartz requires simple cleaning with soap and water or regular household cleaner such as Windex or Formula 409. A magic eraser pad removes some of the metal marks that pans and pots leave on the countertop. Occasional scrubbing with a no-scratch pad and a little SoftScrub is ok to remove hard water residues or for a deep cleaning. Granite and natural stone may be cleaned with a cloth and warm water or with a granite cleaner such as Miracle brand cleaners.

Service and Maintenance

We offer post-installation service and maintenance for a fee starting at a basic service within 50 miles of our location, such as chip repair, seam refill, drill additional hole, attach dishwasher, renew caulk or silicone, etc. Please contact us to get a quote and set an appointment with one of our customer service representatives.

SCHEDULING

Scheduling Times

The measure and installation appointments will be scheduled during normal business hours, Monday to Friday. Please allow 3-hour time window for arrival. The duration of the measure will vary depending on the difficulty of your project. The appointment may take from two to five hours or more. The average installation takes about 4 hours, but it may take the entire day. Please allow enough time for your project.

Appointment Cancellations

Measure appointment cancellations require (1) business day prior notice during normal business hours. Installation appointment cancellations require (2) business days prior notice. If there is a change to an installation date or time, Syverson Tile & Stone is not responsible or liable for any compensatory reimbursements.

Parties and Events

Customers planning an event in their home should be cautioned to provide several weeks of cushion before hosting the event as delays in remodeling and construction projects are common and occur for many unforeseen reasons.

TIMELINE

Lead Time is approximately 8 working days from layout approval to Installation (this can vary depending on workload).

Selection, Design and Purchase

- Select your countertop material, color and edge and finalize design decisions.
- Purchase sink, faucet, soap dispenser, cooktop, vents, and all that goes on the countertop.

Measure Appointment

- Once the order is received, a Syverson Tile & Stone Project Manager will confirm and review the selections and details with you, will check if your cabinets are 100% installed and if all the necessary items are on site, which means you are ready for measure.
- When ready for measure, your Project Manager will give the information to our Measure Tech, who will contact you to set an appointment date.
- At the measure, we request that you are present for important decisions and review.

Approval

- Syverson Tile & Stone will send the Final Quote and Layout Photo, 1-2 days after measure is completed, for review and your approval. We need to receive the **final** version signed to proceed.
- This is our Green Light for fabrication and installation schedule – 8 working days from installation day!

Fabrication

- Once we receive the signed approval and deposit, your Project Manager will submit the order for production scheduling. We can do no changes after this point.

Installation

- Your Project Manager will call you, 2-3 days after, to schedule an installation date.
- One day prior to install, prepare for installation, remove tops, disconnect plumbing.
- Our installation team will install your new countertops and undermount sink and provide warranty and care & maintenance instructions.
- At the end of the installation, we request you are present to inspect and approve.

Post Installation

- The sink and garbage disposal can be connected at least 12 hours after installation.
- After 12 hours, you can wipe, clean, and use your new countertops (not before).

Enjoy your new countertops today (and for many years to come)